



## LOCATION

Doubs, MD

## DATE OF WORK

April 2014

## PROJECT

B-3966

*Transformer from port to foundation*

In April of 2014, HLI coordinated and completed the delivery of a 412,000 lbs transformer to a substation in Doubs, MD. HLI received the unit free on a railcar in Westminster, MD and secured it for travel. The transformer covered the short rail distance and arrived at the substation quickly. At the site, HLI's rigging team went to work.



The crew constructed a temporary pad to support and store the transformer until the substation was ready to integrate it. They then utilized a jack and slide system to move the unit directly from the railcar to the pad. After setting the transformer, the crew unloaded several trucks of transformer accessories into the yard for storage as well. The entire job was completed safely and on time.