



LOCATION

Lambertville, NJ

DATE OF WORK

February 2015

PROJECT

B-5005

Transformer from US border to foundation

This 151,000 lbs transformer began its trip in Laredo, TX where HLI received it loaded on a depressed deck railcar. HLI transported the unit by rail across the country to a rail siding in Flemington, NJ. Once it reached the siding, HLI mobilized a rigging crew to offload the unit from the railcar onto a transport trailer via a crane. The crane encountered no problems during the transload, but the road transport was delayed for a day due to snowy weather conditions.



Once the roads had been cleared the next day, HLI commenced the road transport and hauled the transformer 12 miles to the site. At the substation, HLI used a jack and slide system to move the unit from the transport trailer onto the customer's final pad. The entire project was completed safely and on time.

